



## Ram Restoration

---

2800 East River Road Suite A  
Dayton, Ohio 45439  
RamRestorationUSA.com  
(937) 885-0088

Client: Waynesville City Schools, High School-mitigation  
Business: 723 Dayton Rd  
Waynesville, OH 45068

Operator: ROBBIE

Type of Estimate: Mold contamination

Date Entered: 8/11/2022

Date Assigned:

Price List: OHCI8X\_AUG22

Labor Efficiency: Restoration/Service/Remodel

Estimate: WAYNESVILLE-HS-1



# Ram Restoration

2800 East River Road Suite A  
Dayton, Ohio 45439  
RamRestorationUSA.com  
(937) 885-0088

## WAYNESVILLE-HS-1

### Main Level

#### Main Level


DESCRIPTION	QTY
1. Neg. air fan/Air scrub.-Large (per 24 hr period)-No monit. 18 air scrubbers for 14 days	252.00 DA
2. Add for HEPA filter (for negative air exhaust fan)	7.20 EA
3. Hydroxyl generator - odor counteractant - 2 optics 18 machines for 14 days	252.00 DA
4. Provide box & tape - medium size	150.00 EA
5. Provide box & tape - small size	150.00 EA
6. Scissor lift - 26' platform height (per week)	2.00 WK
7. Dumpster load - Approx. 40 yards, 7-8 tons of debris	8.00 EA
8. Dumpster load - Approx. 12 yards, 1-3 tons of debris	6.00 EA
9. Contamination - air or surface testing & lab analysis	100.00 EA
10. Detach & Reset In-wall / In-ceiling speaker	1.00 EA
11. Exit sign - Detach & reset	50.00 EA
12. Detach & Reset Commercial smoke detector	75.00 EA
13. Detach & Reset Commercial intercom - Remote station	100.00 EA
14. HVAC - General Laborer - per hour Additional hours it took to replace return and supply vents	85.00 HR
15. Electrician - per hour Additional hours it took to complete electrical work	155.00 HR
16. Floor Cleaning Technician - per hour Additional hours it took to complete work	160.00 HR

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



**RM 10**

**Height: 8' 10"**

987.86 SF Walls	772.98 SF Ceiling
1760.84 SF Walls & Ceiling	772.98 SF Floor
85.89 SY Flooring	111.83 LF Floor Perimeter
111.83 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


17. Remove susp. ceiling tile, bag for disp. - after hrs	772.98 SF
18. Material Only Suspended ceiling tile - 2' x 4'	772.98 SF
19. Install Suspended ceiling tile - 2' x 4'	772.98 SF
Labor at standard rate	
20. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	772.98 SF
21. Protect contents - Cover with plastic	1760.84 SF
22. HEPA Vacuuming - Detailed - (PER SF)	772.98 SF
23. Clean more than the floor - Heavy	1760.84 SF
clean all surfaces in room	
24. Clean and deodorize carpet	772.98 SF
25. Apply plant-based anti-microbial agent to more than the floor	1760.84 SF
26. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
27. Clean suspended ceiling grid	772.98 SF
28. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
29. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
30. Clean with pressure/chemical spray	4.00 SF
suspending ceiling return vents	

### NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



**rm 11**

**Height: 8' 10"**

890.69 SF Walls	620.97 SF Ceiling
1511.66 SF Walls & Ceiling	620.97 SF Floor
69.00 SY Flooring	100.83 LF Floor Perimeter
100.83 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


31. Remove susp. ceiling tile, bag for disp. - after hrs	620.97 SF
32. Material Only Suspended ceiling tile - 2' x 4'	620.97 SF
33. Install Suspended ceiling tile - 2' x 4'	620.97 SF
Labor at standard rate	
34. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	620.97 SF
35. Protect contents - Cover with plastic	1511.66 SF
36. HEPA Vacuuming - Detailed - (PER SF)	620.97 SF
37. Clean more than the floor - Heavy	1511.66 SF
clean all surfaces in room	
38. Clean and deodorize carpet	620.97 SF
39. Apply plant-based anti-microbial agent to more than the floor	1511.66 SF
40. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
41. Clean suspended ceiling grid	620.97 SF
42. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
43. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
44. Clean with pressure/chemical spray	4.00 SF
suspending ceiling return vents	

### NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



**RM12**

**Height: 8' 10"**

986.39 SF Walls	770.21 SF Ceiling
1756.59 SF Walls & Ceiling	770.21 SF Floor
85.58 SY Flooring	111.67 LF Floor Perimeter
111.67 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


45. Protect contents - Cover with plastic	1756.59 SF
46. HEPA Vacuuming - Detailed - (PER SF)	770.21 SF
47. Clean more than the floor - Heavy clean all surfaces in room	1756.59 SF
48. Clean and deodorize carpet	770.21 SF
49. Apply plant-based anti-microbial agent to more than the floor	1756.59 SF
50. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
51. Clean suspended ceiling grid	770.21 SF
52. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
53. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
54. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
55. Remove susp. ceiling tile, bag for disp. - after hrs	770.21 SF
56. Material Only Suspended ceiling tile - 2' x 4'	770.21 SF
57. Install Suspended ceiling tile - 2' x 4' Labor at standard rate	770.21 SF
58. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	770.21 SF

### NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### Rm 13

**Height: 8' 10"**

990.81 SF Walls	780.63 SF Ceiling
1771.43 SF Walls & Ceiling	780.63 SF Floor
86.74 SY Flooring	112.17 LF Floor Perimeter
112.17 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


59. Protect contents - Cover with plastic	1771.43 SF
60. HEPA Vacuuming - Detailed - (PER SF)	780.63 SF
61. Clean more than the floor - Heavy clean all surfaces in room	1771.43 SF
62. Clean and deodorize carpet	780.63 SF
63. Apply plant-based anti-microbial agent to more than the floor	1771.43 SF
64. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
65. Clean suspended ceiling grid	780.63 SF
66. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
67. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
68. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
69. Remove susp. ceiling tile, bag for disp. - after hrs	780.63 SF
70. Material Only Suspended ceiling tile - 2' x 4'	780.63 SF
71. Install Suspended ceiling tile - 2' x 4' Labor at standard rate	780.63 SF
72. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	780.63 SF

### NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



**RM14**

**Height: 8' 10"**

986.39 SF Walls	769.53 SF Ceiling
1755.92 SF Walls & Ceiling	769.53 SF Floor
85.50 SY Flooring	111.67 LF Floor Perimeter
111.67 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


73. Protect contents - Cover with plastic	1755.92 SF
74. HEPA Vacuuming - Detailed - (PER SF)	769.53 SF
75. Clean more than the floor - Heavy clean all surfaces in room	1755.92 SF
76. Clean and deodorize carpet	769.53 SF
77. Apply plant-based anti-microbial agent to more than the floor	1755.92 SF
78. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
79. Clean suspended ceiling grid	769.53 SF
80. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
81. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
82. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
83. Remove susp. ceiling tile, bag for disp. - after hrs	769.53 SF
84. Material Only Suspended ceiling tile - 2' x 4'	769.53 SF
85. Install Suspended ceiling tile - 2' x 4' Labor at standard rate	769.53 SF
86. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	769.53 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



**RM15**

**Height: 8' 10"**

886.28 SF Walls	614.25 SF Ceiling
1500.53 SF Walls & Ceiling	614.25 SF Floor
68.25 SY Flooring	100.33 LF Floor Perimeter
100.33 LF Ceil. Perimeter	

### DESCRIPTION

### QTY

87. Protect contents - Cover with plastic	1500.53 SF
88. HEPA Vacuuming - Detailed - (PER SF)	614.25 SF
89. Clean more than the floor - Heavy clean all surfaces in room	1500.53 SF
90. Clean and deodorize carpet	614.25 SF
91. Apply plant-based anti-microbial agent to more than the floor	1500.53 SF
92. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
93. Clean suspended ceiling grid	614.25 SF
94. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
95. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
96. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
97. Remove susp. ceiling tile, bag for disp. - after hrs	614.25 SF
98. Material Only Suspended ceiling tile - 2' x 4'	614.25 SF
99. Install Suspended ceiling tile - 2' x 4' Labor at standard rate	614.25 SF
100. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	614.25 SF


NOTES:





## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### RM16

**Height: 8' 10"**

986.39 SF Walls	769.73 SF Ceiling
1756.12 SF Walls & Ceiling	769.73 SF Floor
85.53 SY Flooring	111.67 LF Floor Perimeter
111.67 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


101. Protect contents - Cover with plastic	1756.12 SF
102. HEPA Vacuuming - Detailed - (PER SF)	769.73 SF
103. Clean more than the floor - Heavy clean all surfaces in room	1756.12 SF
104. Clean and deodorize carpet	769.73 SF
105. Apply plant-based anti-microbial agent to more than the floor	1756.12 SF
106. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
107. Clean suspended ceiling grid	769.73 SF
108. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
109. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
110. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
111. Remove susp. ceiling tile, bag for disp. - after hrs	769.73 SF
112. Material Only Suspended ceiling tile - 2' x 4'	769.73 SF
113. Install Suspended ceiling tile - 2' x 4' Labor at standard rate	769.73 SF
114. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	769.73 SF

### NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



**RM17**

**Height: 8' 10"**

886.28 SF Walls	614.68 SF Ceiling
1500.96 SF Walls & Ceiling	614.68 SF Floor
68.30 SY Flooring	100.33 LF Floor Perimeter
100.33 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


115. Protect contents - Cover with plastic	1500.96 SF
116. HEPA Vacuuming - Detailed - (PER SF)	614.68 SF
117. Clean more than the floor - Heavy clean all surfaces in room	1500.96 SF
118. Clean and deodorize carpet	614.68 SF
119. Apply plant-based anti-microbial agent to more than the floor	1500.96 SF
120. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
121. Clean suspended ceiling grid	614.68 SF
122. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
123. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
124. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
125. Remove susp. ceiling tile, bag for disp. - after hrs	614.68 SF
126. Material Only Suspended ceiling tile - 2' x 4'	614.68 SF
127. Install Suspended ceiling tile - 2' x 4' Labor at standard rate	614.68 SF
128. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	614.68 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



Missing Wall


### Stairs

Height: 17'

240.92 SF Walls	51.04 SF Ceiling
291.96 SF Walls & Ceiling	80.73 SF Floor
8.97 SY Flooring	18.06 LF Floor Perimeter
16.33 LF Ceil. Perimeter	

6' 3" X 17'

Opens into BOTTOM\_OF\_LE



Missing Wall


### Subroom: Stairs2 (1)

Height: 12' 6"

231.87 SF Walls	56.39 SF Ceiling
288.26 SF Walls & Ceiling	86.92 SF Floor
9.66 SY Flooring	25.03 LF Floor Perimeter
23.67 LF Ceil. Perimeter	

5' 10" X 12' 6"

Opens into LANDING



Missing Wall

### Subroom: Landing (2)

Height: 12' 6"

330.21 SF Walls	87.13 SF Ceiling
417.33 SF Walls & Ceiling	87.13 SF Floor
9.68 SY Flooring	26.42 LF Floor Perimeter
26.42 LF Ceil. Perimeter	

Missing Wall

5' 10" X 12' 6"

Opens into STAIRS2

6' 3" X 12' 6"

Opens into STAIRS

### DESCRIPTION

QTY

129. Scaffolding Setup & Take down - per hour	4.00 HR
130. Scaffold - per section (per day)	6.00 DA
131. Additional cost for high wall or ceiling - Over 14'	1.00 SF
132. R&R Surveillance system - cameras, monitors, etc.	1.00 EA
133. Detach & Reset Commercial smoke detector	1.00 EA
134. Protect contents - Cover with plastic	802.99 SF
135. HEPA Vacuuming - Detailed - (PER SF)	254.77 SF
136. Clean more than the floor - Heavy	1057.77 SF
137. Clean floor - tile - Heavy clean	254.77 SF
138. Apply plant-based anti-microbial agent to the walls	802.99 SF
139. Clean suspended ceiling grid	194.56 SF




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Stairs

DESCRIPTION	QTY
140. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
141. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
142. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
143. Remove susp. ceiling tile, bag for disp. - after hrs	194.56 SF
144. Material Only Suspended ceiling tile - 2' x 4'	194.56 SF
145. Install Suspended ceiling tile - 2' x 4'	194.56 SF
Labor at standard rate	
146. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	254.77 SF

NOTES:



### Bottom of left stairs

Height: 8' 10"

401.54 SF Walls	152.73 SF Ceiling
554.27 SF Walls & Ceiling	152.73 SF Floor
16.97 SY Flooring	45.42 LF Floor Perimeter
45.42 LF Ceil. Perimeter	

Missing Wall

6' 3" X 8' 10"

Opens into STAIRS

DESCRIPTION	QTY
147. Protect contents - Cover with plastic	554.27 SF
148. HEPA Vacuuming - Detailed - (PER SF)	152.73 SF
149. Clean floor - tile - Heavy clean	152.73 SF
150. Clean more than the floor - Heavy	554.27 SF
151. Apply plant-based anti-microbial agent to the walls	401.54 SF
152. Electrician - per hour	1.00 HR




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Bottom of left stairs

DESCRIPTION	QTY
153. Clean suspended ceiling grid	152.73 SF
154. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
155. Remove susp. ceiling tile, bag for disp. - after hrs	152.73 SF
156. Material Only Suspended ceiling tile - 2' x 4'	152.73 SF
157. Install Suspended ceiling tile - 2' x 4'	152.73 SF
Labor at standard rate	
158. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	152.73 SF

NOTES:



### left stairwell corridor

Height: 8' 10"

337.14 SF Walls	157.00 SF Ceiling
494.14 SF Walls & Ceiling	157.00 SF Floor
17.44 SY Flooring	38.17 LF Floor Perimeter
38.17 LF Ceil. Perimeter	

Missing Wall

12' X 8' 10"

Opens into LEFT\_CORRIDO

DESCRIPTION	QTY
159. Protect contents - Cover with plastic	494.14 SF
160. Clean floor - tile - Heavy clean	157.00 SF
161. HEPA Vacuuming - Detailed - (PER SF)	157.00 SF
162. Clean more than the floor - Heavy	494.14 SF
163. Clean and deodorize carpet	157.00 SF
164. Apply plant-based anti-microbial agent to the walls	337.14 SF
165. Electrician - per hour	1.00 HR
166. Clean suspended ceiling grid	157.00 SF



# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - left stairwell corridor

DESCRIPTION	QTY
167. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
168. Remove susp. ceiling tile, bag for disp. - after hrs	157.00 SF
169. Material Only Suspended ceiling tile - 2' x 4'	157.00 SF
170. Install Suspended ceiling tile - 2' x 4'	157.00 SF
Labor at standard rate	
171. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	157.00 SF

NOTES:

**Left corridor**

**Height: 8' 10"**

2747.46 SF Walls	1894.89 SF Ceiling
4642.35 SF Walls & Ceiling	1894.89 SF Floor
210.54 SY Flooring	308.56 LF Floor Perimeter
318.64 LF Ceil. Perimeter	

Missing Wall	12' X 8' 10"	Opens into LEFT_STAIRWE
Missing Wall	12' X 8' 10"	Opens into POCTAGON_2
Missing Wall - Goes to Floor	4' 9" X 6' 8"	Opens into WOMANS_BATH_
Missing Wall - Goes to Floor	5' 4" X 6' 8"	Opens into MENS_BATH_2

DESCRIPTION	QTY
172. Protect contents - Cover with plastic	4642.35 SF
173. HEPA Vacuuming - Detailed - (PER SF)	1894.89 SF
174. Clean more than the floor - Heavy	4642.35 SF
175. Apply plant-based anti-microbial agent to the walls	2747.46 SF
176. Clean suspended ceiling grid	1894.89 SF
177. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
178. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Left corridor

DESCRIPTION	QTY
179. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
180. Clean floor - tile - Heavy clean	1894.89 SF
181. Remove susp. ceiling tile, bag for disp. - after hrs	1894.89 SF
182. Material Only Suspended ceiling tile - 2' x 4'	1894.89 SF
183. Install Suspended ceiling tile - 2' x 4'	1894.89 SF
Labor at standard rate	
184. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	1894.89 SF

NOTES:



### teachers break rm

Height: 8' 10"

774.39 SF Walls	475.65 SF Ceiling
1250.03 SF Walls & Ceiling	475.65 SF Floor
52.85 SY Flooring	87.67 LF Floor Perimeter
87.67 LF Ceil. Perimeter	

DESCRIPTION	QTY
185. Protect contents - Cover with plastic	1250.03 SF
186. HEPA Vacuuming - Detailed - (PER SF)	475.65 SF
187. Clean more than the floor - Heavy	1250.03 SF
188. Clean and deodorize carpet	475.65 SF
189. Apply plant-based anti-microbial agent to the walls	774.39 SF
190. Clean with pressure/chemical spray	4.00 SF
191. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
192. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - teachers break rm

DESCRIPTION	QTY
193. Clean suspended ceiling grid	475.65 SF
194. Remove susp. ceiling tile, bag for disp. - after hrs	475.65 SF
195. Material Only Suspended ceiling tile - 2' x 4'	475.65 SF
196. Install Suspended ceiling tile - 2' x 4'	475.65 SF
Labor at standard rate	
197. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	475.65 SF

NOTES:



#### MEns bath 1

Height: 8' 10"

668.17 SF Walls	298.33 SF Ceiling
966.50 SF Walls & Ceiling	298.33 SF Floor
33.15 SY Flooring	74.33 LF Floor Perimeter
79.67 LF Ceil. Perimeter	

Missing Wall - Goes to Floor

5' 4" X 6' 8"

Opens into LEFT\_CORRIDO

DESCRIPTION	QTY
198. Protect contents - Cover with plastic	966.50 SF
199. HEPA Vacuuming - Detailed - (PER SF)	298.33 SF
200. Clean more than the floor - Heavy	966.50 SF
201. Apply plant-based anti-microbial agent to the walls	668.17 SF
202. Clean floor - tile - Heavy clean	298.33 SF
203. Remove susp. ceiling tile, bag for disp. - after hrs	298.33 SF
204. Material Only Suspended ceiling tile - 2' x 4'	298.33 SF
205. Install Suspended ceiling tile - 2' x 4'	298.33 SF
Labor at standard rate	





# Ram Restoration


2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - MENS bath 1

DESCRIPTION	QTY
-------------	-----

206. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	298.33 SF
---	-----------

NOTES:



### Womans bath 1

Height: 8' 10"

673.53 SF Walls	300.82 SF Ceiling
974.35 SF Walls & Ceiling	300.82 SF Floor
33.42 SY Flooring	75.08 LF Floor Perimeter
79.83 LF Ceil. Perimeter	

Missing Wall - Goes to Floor

4' 9" X 6' 8"

Opens into LEFT\_CORRIDO

DESCRIPTION	QTY
-------------	-----

207. Protect contents - Cover with plastic	974.35 SF
208. HEPA Vacuuming - Detailed - (PER SF)	300.82 SF
209. Clean more than the floor - Heavy	974.35 SF
210. Apply plant-based anti-microbial agent to the walls	673.53 SF
211. Electrician - per hour	1.00 HR
212. Clean floor - tile - Heavy clean	300.82 SF
213. Remove susp. ceiling tile, bag for disp. - after hrs	300.82 SF
214. Material Only Suspended ceiling tile - 2' x 4'	300.82 SF
215. Install Suspended ceiling tile - 2' x 4'	300.82 SF
Labor at standard rate	
216. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	300.82 SF




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Womans bath 1

DESCRIPTION	QTY
-------------	-----

NOTES:



**T.R.**

**Height: 9'**

286.50 SF Walls	59.17 SF Ceiling
345.67 SF Walls & Ceiling	59.17 SF Floor
6.57 SY Flooring	31.83 LF Floor Perimeter
31.83 LF Ceil. Perimeter	

DESCRIPTION	QTY
-------------	-----

217. Protect contents - Cover with plastic	345.67 SF
218. HEPA Vacuuming - Detailed - (PER SF)	59.17 SF
219. Clean more than the floor - Heavy clean all surfaces in room	345.67 SF
220. Clean and deodorize carpet	59.17 SF
221. Apply plant-based anti-microbial agent to more than the floor	345.67 SF
222. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
223. Clean suspended ceiling grid	59.17 SF
224. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
225. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
226. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
227. Remove susp. ceiling tile, bag for disp. - after hrs	59.17 SF
228. Material Only Suspended ceiling tile - 2' x 4'	59.17 SF
229. Install Suspended ceiling tile - 2' x 4'	59.17 SF
Labor at standard rate	



## Ram Restoration


2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - T.R.

DESCRIPTION	QTY
-------------	-----

230. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	59.17 SF
---	----------

NOTES:



**office bath 1**

**Height: 9'**

246.00 SF Walls	45.69 SF Ceiling
291.69 SF Walls & Ceiling	45.69 SF Floor
5.08 SY Flooring	27.33 LF Floor Perimeter
27.33 LF Ceil. Perimeter	

DESCRIPTION	QTY
-------------	-----

231. Protect contents - Cover with plastic	291.69 SF
232. HEPA Vacuuming - Detailed - (PER SF)	45.69 SF
233. Clean more than the floor - Heavy	291.69 SF
234. Clean floor - tile - Heavy clean	45.69 SF
235. Apply plant-based anti-microbial agent to the walls	246.00 SF
236. Clean suspended ceiling grid	45.69 SF
237. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
238. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
239. Clean with pressure/chemical spray	4.00 SF
240. Remove susp. ceiling tile, bag for disp. - after hrs	45.69 SF
241. Material Only Suspended ceiling tile - 2' x 4'	45.69 SF
242. Install Suspended ceiling tile - 2' x 4'	45.69 SF
Labor at standard rate	
243. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	45.69 SF



## Ram Restoration


2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - office bath 1

#### DESCRIPTION

#### QTY

NOTES:



#### office bath 2

Height: 9'

239.33 SF Walls	44.81 SF Ceiling
284.14 SF Walls & Ceiling	44.81 SF Floor
4.98 SY Flooring	26.59 LF Floor Perimeter
26.59 LF Ceil. Perimeter	

#### DESCRIPTION

#### QTY

244. Protect contents - Cover with plastic	284.14 SF
245. HEPA Vacuuming - Detailed - (PER SF)	44.81 SF
246. Clean more than the floor - Heavy	284.14 SF
247. Clean floor - tile - Heavy clean	44.81 SF
248. Apply plant-based anti-microbial agent to the walls	239.33 SF
249. Clean suspended ceiling grid	44.81 SF
250. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
251. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
252. Clean with pressure/chemical spray	4.00 SF
253. Remove susp. ceiling tile, bag for disp. - after hrs	44.81 SF
254. Material Only Suspended ceiling tile - 2' x 4'	44.81 SF
255. Install Suspended ceiling tile - 2' x 4'	44.81 SF
Labor at standard rate	
256. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	44.81 SF



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - office bath 2

DESCRIPTION	QTY
-------------	-----

NOTES:

Office corridor	Height: 9'								
	<table style="width:100%; border-collapse: collapse;"> <tr> <td style="width: 50%;">361.50 SF Walls</td> <td style="width: 50%; text-align: right;">81.69 SF Ceiling</td> </tr> <tr> <td>443.19 SF Walls &amp; Ceiling</td> <td style="text-align: right;">81.69 SF Floor</td> </tr> <tr> <td>9.08 SY Flooring</td> <td style="text-align: right;">40.17 LF Floor Perimeter</td> </tr> <tr> <td>40.17 LF Ceil. Perimeter</td> <td></td> </tr> </table>	361.50 SF Walls	81.69 SF Ceiling	443.19 SF Walls & Ceiling	81.69 SF Floor	9.08 SY Flooring	40.17 LF Floor Perimeter	40.17 LF Ceil. Perimeter	
361.50 SF Walls	81.69 SF Ceiling								
443.19 SF Walls & Ceiling	81.69 SF Floor								
9.08 SY Flooring	40.17 LF Floor Perimeter								
40.17 LF Ceil. Perimeter									

DESCRIPTION	QTY
-------------	-----

257. Protect contents - Cover with plastic	443.19 SF
258. HEPA Vacuuming - Detailed - (PER SF)	81.69 SF
259. Clean more than the floor - Heavy clean all surfaces in room	443.19 SF
260. Clean and deodorize carpet	81.69 SF
261. Apply plant-based anti-microbial agent to more than the floor	443.19 SF
262. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	2.00 HR
263. Clean suspended ceiling grid	81.69 SF
264. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
265. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
266. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
267. Remove susp. ceiling tile, bag for disp. - after hrs	81.69 SF
268. Material Only Suspended ceiling tile - 2' x 4'	81.69 SF
269. Install Suspended ceiling tile - 2' x 4'	81.69 SF
Labor at standard rate	




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Office corridor

DESCRIPTION	QTY
270. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	81.69 SF

NOTES:



Counselor	Height: 9'
451.50 SF Walls	153.78 SF Ceiling
605.28 SF Walls & Ceiling	153.78 SF Floor
17.09 SY Flooring	50.17 LF Floor Perimeter
50.17 LF Ceil. Perimeter	

DESCRIPTION	QTY
271. HEPA Vacuuming - Detailed - (PER SF)	153.78 SF
272. Protect contents - Cover with plastic	605.28 SF
273. Clean more than the floor - Heavy clean all surfaces in room	605.28 SF
274. Clean and deodorize carpet	153.78 SF
275. Apply plant-based anti-microbial agent to more than the floor	605.28 SF
276. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	2.00 HR
277. Clean suspended ceiling grid	153.78 SF
278. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
279. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
280. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
281. Remove susp. ceiling tile, bag for disp. - after hrs	153.78 SF
282. Material Only Suspended ceiling tile - 2' x 4'	153.78 SF




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Counselor

DESCRIPTION	QTY
283. Install Suspended ceiling tile - 2' x 4' Labor at standard rate	153.78 SF
284. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	153.78 SF

NOTES:



clinic

Height: 9'

455.77 SF Walls	149.01 SF Ceiling
604.79 SF Walls & Ceiling	149.01 SF Floor
16.56 SY Flooring	50.64 LF Floor Perimeter
50.64 LF Ceil. Perimeter	

DESCRIPTION	QTY
285. Protect contents - Cover with plastic	604.79 SF
286. HEPA Vacuuming - Detailed - (PER SF)	149.01 SF
287. Clean more than the floor - Heavy clean all surfaces in room	604.79 SF
288. Clean and deodorize carpet	149.01 SF
289. Apply plant-based anti-microbial agent to more than the floor	604.79 SF
290. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	1.00 HR
291. Clean suspended ceiling grid	149.01 SF
292. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
293. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
294. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - clinic

DESCRIPTION	QTY
295. Remove susp. ceiling tile, bag for disp. - after hrs	149.01 SF
296. Material Only Suspended ceiling tile - 2' x 4'	149.01 SF
297. Install Suspended ceiling tile - 2' x 4'	149.01 SF
Labor at standard rate	
298. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	149.01 SF

NOTES:



### pOctagon 2

Height: 9' 11"

601.18 SF Walls	479.37 SF Ceiling
1080.55 SF Walls & Ceiling	479.37 SF Floor
53.26 SY Flooring	59.31 LF Floor Perimeter
71.31 LF Ceil. Perimeter	

Missing Wall

12' X 9' 11"

Opens into LEFT\_CORRIDO

Missing Wall

8' 10 1/8" X 9' 11"

Opens into Exterior

DESCRIPTION	QTY
299. Protect contents - Cover with plastic	1080.55 SF
300. HEPA Vacuuming - Detailed - (PER SF)	479.37 SF
301. Clean more than the floor - Heavy	1080.55 SF
302. Clean floor - tile - Heavy clean	479.37 SF
303. Apply plant-based anti-microbial agent to the walls	601.18 SF
304. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
305. Clean suspended ceiling grid	479.37 SF
306. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA






## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - pOctagon 2

DESCRIPTION	QTY
307. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
308. Clean with pressure/chemical spray	4.00 SF
309. Remove susp. ceiling tile, bag for disp. - after hrs	479.37 SF
310. Material Only Suspended ceiling tile - 2' x 4'	479.37 SF
311. Install Suspended ceiling tile - 2' x 4'	479.37 SF
Labor at standard rate	
312. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	479.37 SF

NOTES:



**Office**

**Height: 9'**

451.42 SF Walls	162.60 SF Ceiling
614.02 SF Walls & Ceiling	162.60 SF Floor
18.07 SY Flooring	50.16 LF Floor Perimeter
50.16 LF Ceil. Perimeter	

DESCRIPTION	QTY
313. Protect contents - Cover with plastic	614.02 SF
314. HEPA Vacuuming - Detailed - (PER SF)	162.60 SF
315. Clean more than the floor - Heavy clean all surfaces in room	614.02 SF
316. Clean and deodorize carpet	162.60 SF
317. Apply plant-based anti-microbial agent to more than the floor	614.02 SF
318. Content Manipulation charge - per hour	2.00 HR
Box everything in the cabinets Remove everything on walls and clean	
319. Clean suspended ceiling grid	162.60 SF




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Office

DESCRIPTION	QTY
320. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
321. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
322. Clean with pressure/chemical spray suspending ceiling return vents	8.00 SF
323. Remove susp. ceiling tile, bag for disp. - after hrs	162.60 SF
324. Material Only Suspended ceiling tile - 2' x 4'	162.60 SF
325. Install Suspended ceiling tile - 2' x 4'	162.60 SF
Labor at standard rate	
326. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	162.60 SF

NOTES:



### Principle

Height: 9'

616.95 SF Walls	241.41 SF Ceiling
858.36 SF Walls & Ceiling	241.41 SF Floor
26.82 SY Flooring	68.55 LF Floor Perimeter
68.55 LF Ceil. Perimeter	

DESCRIPTION	QTY
327. Protect contents - Cover with plastic	858.36 SF
328. HEPA Vacuuming - Detailed - (PER SF)	241.41 SF
329. Clean more than the floor - Heavy clean all surfaces in room	858.36 SF
330. Clean and deodorize carpet	241.41 SF
331. Apply plant-based anti-microbial agent to more than the floor	858.36 SF
332. Content Manipulation charge - per hour	2.00 HR




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Principle

DESCRIPTION	QTY
Box everything in the cabinets	
Remove everything on walls and clean	
333. Clean suspended ceiling grid	241.41 SF
334. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
335. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
336. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
337. Remove susp. ceiling tile, bag for disp. - after hrs	241.41 SF
338. Material Only Suspended ceiling tile - 2' x 4'	241.41 SF
339. Install Suspended ceiling tile - 2' x 4'	241.41 SF
Labor at standard rate	
340. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	241.41 SF

NOTES:



**Office**

**Height: 9'**

468.72 SF Walls	174.46 SF Ceiling
643.18 SF Walls & Ceiling	174.46 SF Floor
19.38 SY Flooring	52.08 LF Floor Perimeter
52.08 LF Ceil. Perimeter	

DESCRIPTION	QTY
341. Protect contents - Cover with plastic	643.18 SF
342. HEPA Vacuuming - Detailed - (PER SF)	174.46 SF
343. Clean more than the floor - Heavy clean all surfaces in room	643.18 SF
344. Clean and deodorize carpet	174.46 SF




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Office

DESCRIPTION	QTY
345. Apply plant-based anti-microbial agent to more than the floor	643.18 SF
346. Content Manipulation charge - per hour	2.00 HR
Box everything in the cabinets Remove everything on walls and clean	
347. Clean suspended ceiling grid	174.46 SF
348. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
349. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
350. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
351. Remove susp. ceiling tile, bag for disp. - after hrs	174.46 SF
352. Material Only Suspended ceiling tile - 2' x 4'	174.46 SF
353. Install Suspended ceiling tile - 2' x 4'	174.46 SF
Labor at standard rate	
354. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	174.46 SF

NOTES:



**AD**

**Height: 9'**

475.55 SF Walls	170.32 SF Ceiling
645.88 SF Walls & Ceiling	170.32 SF Floor
18.92 SY Flooring	52.84 LF Floor Perimeter
52.84 LF Ceil. Perimeter	

DESCRIPTION	QTY
355. Protect contents - Cover with plastic	645.88 SF
356. HEPA Vacuuming - Detailed - (PER SF)	170.32 SF
357. Clean more than the floor - Heavy	645.88 SF




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - AD

DESCRIPTION	QTY
clean all surfaces in room	
358. Clean and deodorize carpet	170.32 SF
359. Apply plant-based anti-microbial agent to more than the floor	645.88 SF
360. Content Manipulation charge - per hour	1.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
361. Clean suspended ceiling grid	170.32 SF
362. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
363. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
364. Clean with pressure/chemical spray	4.00 SF
suspending ceiling return vents	
365. Remove susp. ceiling tile, bag for disp. - after hrs	170.32 SF
366. Material Only Suspended ceiling tile - 2' x 4'	170.32 SF
367. Install Suspended ceiling tile - 2' x 4'	170.32 SF
Labor at standard rate	
368. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	170.32 SF

NOTES:



**work room**

**Height: 9'**

512.38 SF Walls	195.64 SF Ceiling
708.02 SF Walls & Ceiling	195.64 SF Floor
21.74 SY Flooring	56.93 LF Floor Perimeter
56.93 LF Ceil. Perimeter	

DESCRIPTION	QTY
369. Protect contents - Cover with plastic	708.02 SF



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088


### CONTINUED - work room

DESCRIPTION	QTY
370. HEPA Vacuuming - Detailed - (PER SF)	195.64 SF
371. Clean more than the floor - Heavy clean all surfaces in room	708.02 SF
372. Clean and deodorize carpet	195.64 SF
373. Apply plant-based anti-microbial agent to more than the floor	708.02 SF
374. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
375. Clean suspended ceiling grid	195.64 SF
376. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
377. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
378. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
379. Remove susp. ceiling tile, bag for disp. - after hrs	195.64 SF
380. Material Only Suspended ceiling tile - 2' x 4'	195.64 SF
381. Install Suspended ceiling tile - 2' x 4' Labor at standard rate	195.64 SF
382. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	195.64 SF

NOTES:

### office hall

Height: 9'



552.58 SF Walls	122.00 SF Ceiling
674.59 SF Walls & Ceiling	122.00 SF Floor
13.56 SY Flooring	61.40 LF Floor Perimeter
61.40 LF Ceil. Perimeter	



# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



## Subroom: Room30 (1)

**Height: 9'**

587.12 SF Walls	133.32 SF Ceiling
720.45 SF Walls & Ceiling	133.32 SF Floor
14.81 SY Flooring	65.24 LF Floor Perimeter
65.24 LF Ceil. Perimeter	

Missing Wall                                    **3/16" X 9'**                                    **Opens into Exterior**  
 Missing Wall                                    **3' 8" X 9'**                                    **Opens into OFFICE\_HALL**


DESCRIPTION	QTY
383. Protect contents - Cover with plastic	1395.03 SF
384. HEPA Vacuuming - Detailed - (PER SF)	255.33 SF
385. Clean more than the floor - Heavy clean all surfaces in room	1395.03 SF
386. Clean and deodorize carpet	255.33 SF
387. Apply plant-based anti-microbial agent to more than the floor	1395.03 SF
388. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
389. Clean suspended ceiling grid	255.33 SF
390. Remove susp. ceiling tile, bag for disp. - after hrs	255.33 SF
391. Material Only Suspended ceiling tile - 2' x 4'	255.33 SF
392. Install Suspended ceiling tile - 2' x 4'	255.33 SF
Labor at standard rate	
393. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	255.33 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### records

**Height: 9'**

393.81 SF Walls	110.02 SF Ceiling
503.84 SF Walls & Ceiling	110.02 SF Floor
12.22 SY Flooring	43.76 LF Floor Perimeter
43.76 LF Ceil. Perimeter	

### DESCRIPTION

### QTY

394. Protect contents - Cover with plastic	503.84 SF
395. HEPA Vacuuming - Detailed - (PER SF)	110.02 SF
396. Clean more than the floor - Heavy clean all surfaces in room	503.84 SF
397. Clean and deodorize carpet	110.02 SF
398. Apply plant-based anti-microbial agent to more than the floor	503.84 SF
399. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	1.00 HR
400. Clean suspended ceiling grid	110.02 SF
401. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
402. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
403. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
404. Remove susp. ceiling tile, bag for disp. - after hrs	110.02 SF
405. Material Only Suspended ceiling tile - 2' x 4'	110.02 SF
406. Install Suspended ceiling tile - 2' x 4'	110.02 SF
Labor at standard rate	
407. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	110.02 SF


### NOTES:





## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### Officer office

**Height: 9'**

319.51 SF Walls	77.09 SF Ceiling
396.60 SF Walls & Ceiling	77.09 SF Floor
8.57 SY Flooring	35.50 LF Floor Perimeter
35.50 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


408. Protect contents - Cover with plastic	396.60 SF
409. HEPA Vacuuming - Detailed - (PER SF)	77.09 SF
410. Clean more than the floor - Heavy clean all surfaces in room	396.60 SF
411. Clean and deodorize carpet	77.09 SF
412. Apply plant-based anti-microbial agent to more than the floor	396.60 SF
413. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	1.00 HR
414. Clean suspended ceiling grid	77.09 SF
415. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
416. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
417. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
418. Remove susp. ceiling tile, bag for disp. - after hrs	77.09 SF
419. Material Only Suspended ceiling tile - 2' x 4'	77.09 SF
420. Install Suspended ceiling tile - 2' x 4' Labor at standard rate	77.09 SF
421. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	77.09 SF

NOTES:



# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



## Admin office

**Height: 9' 6"**

1015.63 SF Walls	754.46 SF Ceiling
1770.09 SF Walls & Ceiling	754.46 SF Floor
83.83 SY Flooring	106.91 LF Floor Perimeter
106.91 LF Ceil. Perimeter	

## DESCRIPTION

## QTY


422. Protect contents - Cover with plastic	1770.09 SF
423. HEPA Vacuuming - Detailed - (PER SF)	754.46 SF
424. Clean more than the floor - Heavy clean all surfaces in room	1770.09 SF
425. Clean and deodorize carpet	754.46 SF
426. Apply plant-based anti-microbial agent to more than the floor	1770.09 SF
427. Content Manipulation charge - per hour	1.00 HR
Box everything in the cabinets Remove everything on walls and clean	
428. Clean suspended ceiling grid	754.46 SF
429. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
430. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
431. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
432. Remove susp. ceiling tile, bag for disp. - after hrs	754.46 SF
433. Material Only Suspended ceiling tile - 2' x 4'	754.46 SF
434. Install Suspended ceiling tile - 2' x 4'	754.46 SF
Labor at standard rate	
435. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	754.46 SF

## NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### Storage Area/Room

Height: 9'

292.35 SF Walls	45.26 SF Ceiling
337.62 SF Walls & Ceiling	45.26 SF Floor
5.03 SY Flooring	32.48 LF Floor Perimeter
32.48 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


436. Protect contents - Cover with plastic	337.62 SF
437. HEPA Vacuuming - Detailed - (PER SF)	45.26 SF
438. Clean more than the floor - Heavy clean all surfaces in room	337.62 SF
439. Clean and deodorize carpet	45.26 SF
440. Apply plant-based anti-microbial agent to more than the floor	337.62 SF
441. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	1.00 HR
442. Clean suspended ceiling grid	45.26 SF
443. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
444. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
445. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
446. Remove susp. ceiling tile, bag for disp. - after hrs	45.26 SF
447. Material Only Suspended ceiling tile - 2' x 4'	45.26 SF
448. Install Suspended ceiling tile - 2' x 4'	45.26 SF
Labor at standard rate	
449. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	45.26 SF

### NOTES:



# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



## admin storage

Height: 8'

450.18 SF Walls	115.68 SF Ceiling
565.86 SF Walls & Ceiling	115.68 SF Floor
12.85 SY Flooring	56.27 LF Floor Perimeter
56.27 LF Ceil. Perimeter	

## DESCRIPTION

## QTY


450. Protect contents - Cover with plastic	565.86 SF
451. HEPA Vacuuming - Detailed - (PER SF)	115.68 SF
452. Clean more than the floor - Heavy clean all surfaces in room	565.86 SF
453. Clean and deodorize carpet	115.68 SF
454. Apply plant-based anti-microbial agent to more than the floor	565.86 SF
455. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	1.00 HR
456. Clean suspended ceiling grid	115.68 SF
457. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
458. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
459. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
460. Remove susp. ceiling tile, bag for disp. - after hrs	115.68 SF
461. Material Only Suspended ceiling tile - 2' x 4'	115.68 SF
462. Install Suspended ceiling tile - 2' x 4'	115.68 SF
Labor at standard rate	
463. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	115.68 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### octagon 1

**Height: 9' 11"**

587.60 SF Walls	520.03 SF Ceiling
1107.63 SF Walls & Ceiling	520.03 SF Floor
57.78 SY Flooring	54.47 LF Floor Perimeter
83.59 LF Ceil. Perimeter	

Missing Wall	8' 4 3/4" X 9' 11"	Opens into CORRIDOR_1
Missing Wall	7' 5 1/8" X 9' 11"	Opens into FRONT_ENTRAN
Missing Wall	13' 3 1/2" X 9' 11"	Opens into FRONT_ENTRAN

### DESCRIPTION

### QTY


464. Protect contents - Cover with plastic	1107.63 SF
465. HEPA Vacuuming - Detailed - (PER SF)	520.03 SF
466. Clean more than the floor - Heavy	1107.63 SF
467. Clean floor - tile - Heavy clean	520.03 SF
468. Apply plant-based anti-microbial agent to the walls	587.60 SF
469. Clean suspended ceiling grid	520.03 SF
470. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
471. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
472. Clean with pressure/chemical spray	4.00 SF
473. Remove susp. ceiling tile, bag for disp. - after hrs	520.03 SF
474. Material Only Suspended ceiling tile - 2' x 4'	520.03 SF
475. Install Suspended ceiling tile - 2' x 4'	520.03 SF
Labor at standard rate	
476. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	520.03 SF

### NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### corridor 1

**Height: 9'**

542.97 SF Walls	223.68 SF Ceiling
766.65 SF Walls & Ceiling	223.68 SF Floor
24.85 SY Flooring	60.33 LF Floor Perimeter
60.33 LF Ceil. Perimeter	

**Missing Wall**

**8' 4 3/4" X 9'**

**Opens into OCTAGON\_1**

### DESCRIPTION

**QTY**


477. Protect contents - Cover with plastic	766.65 SF
478. HEPA Vacuuming - Detailed - (PER SF)	223.68 SF
479. Clean more than the floor - Heavy	766.65 SF
480. Clean floor - tile - Heavy clean	223.68 SF
481. Apply plant-based anti-microbial agent to the walls	542.97 SF
482. Clean suspended ceiling grid	223.68 SF
483. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
484. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
485. Clean with pressure/chemical spray	4.00 SF
486. Remove susp. ceiling tile, bag for disp. - after hrs	223.68 SF
487. Material Only Suspended ceiling tile - 2' x 4'	223.68 SF
488. Install Suspended ceiling tile - 2' x 4'	223.68 SF
Labor at standard rate	
489. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	223.68 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### Baack Corridor

**Height: 8'**

603.66 SF Walls	363.51 SF Ceiling
967.16 SF Walls & Ceiling	363.51 SF Floor
40.39 SY Flooring	75.46 LF Floor Perimeter
75.46 LF Ceil. Perimeter	

Missing Wall

**13' 10 11/16" X 8'**

**Opens into Exterior**

### DESCRIPTION

### QTY


490. Protect contents - Cover with plastic	967.16 SF
491. HEPA Vacuuming - Detailed - (PER SF)	363.51 SF
492. Clean more than the floor - Heavy	967.16 SF
493. Clean floor - tile - Heavy clean	363.51 SF
494. Apply plant-based anti-microbial agent to the walls	603.66 SF
495. Clean suspended ceiling grid	363.51 SF
496. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
497. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
498. Clean with pressure/chemical spray	4.00 SF
499. Remove susp. ceiling tile, bag for disp. - after hrs	363.51 SF
500. Material Only Suspended ceiling tile - 2' x 4'	363.51 SF
501. Install Suspended ceiling tile - 2' x 4'	363.51 SF
Labor at standard rate	
502. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	363.51 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### front entrance

**Height: 8'**

607.86 SF Walls	686.66 SF Ceiling
1294.52 SF Walls & Ceiling	686.66 SF Floor
76.30 SY Flooring	75.98 LF Floor Perimeter
75.98 LF Ceil. Perimeter	

Missing Wall	7' 5 1/8" X 8'	Opens into OCTAGON_1
Missing Wall	13' 3 1/2" X 8'	Opens into OCTAGON_1
Missing Wall	18' 1 1/2" X 8'	Opens into RIGHT_ENTRAN

### DESCRIPTION

### QTY

503. Protect contents - Cover with plastic	1294.52 SF
504. HEPA Vacuuming - Detailed - (PER SF)	686.66 SF
505. Clean more than the floor - Heavy	1294.52 SF
506. Clean floor - tile - Heavy clean	686.66 SF
507. Apply plant-based anti-microbial agent to the walls	607.86 SF
508. Clean suspended ceiling grid	686.66 SF
509. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
510. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
511. Clean with pressure/chemical spray	4.00 SF
512. Remove susp. ceiling tile, bag for disp. - after hrs	686.66 SF
513. Material Only Suspended ceiling tile - 2' x 4'	686.66 SF
514. Install Suspended ceiling tile - 2' x 4'	686.66 SF
Labor at standard rate	
515. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	686.66 SF

### NOTES:







## Ram Restoration

2800 East River Road Suite A  
Dayton, Ohio 45439  
RamRestorationUSA.com  
(937) 885-0088

### CONTINUED - Concessions


DESCRIPTION	QTY
529. Protect contents - Cover with plastic	866.89 SF
530. HEPA Vacuuming - Detailed - (PER SF)	190.96 SF
531. Clean more than the floor - Heavy	866.89 SF
532. Clean floor - tile - Heavy clean	190.96 SF
533. Apply plant-based anti-microbial agent to the walls	675.93 SF
534. Content Manipulation charge - per hour	2.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
535. Clean suspended ceiling grid	190.96 SF
536. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
537. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
538. Clean with pressure/chemical spray	4.00 SF
539. Remove susp. ceiling tile, bag for disp. - after hrs	190.96 SF
540. Material Only Suspended ceiling tile - 2' x 4'	190.96 SF
541. Install Suspended ceiling tile - 2' x 4'	190.96 SF
Labor at standard rate	
542. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	190.96 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### Right entrance

**Height: 8'**

916.10 SF Walls	1039.12 SF Ceiling
1955.22 SF Walls & Ceiling	1039.12 SF Floor
115.46 SY Flooring	113.68 LF Floor Perimeter
118.68 LF Ceil. Perimeter	

<b>Missing Wall</b>	<b>11' 10" X 8'</b>	<b>Opens into MEDIA_CENTER</b>
<b>Missing Wall - Goes to Floor</b>	<b>5' X 6' 8"</b>	<b>Opens into WOMANS_RESTR</b>
<b>Missing Wall</b>	<b>4' 11 1/2" X 8'</b>	<b>Opens into MENS_RESTROO</b>
<b>Missing Wall</b>	<b>18' 1 1/2" X 8'</b>	<b>Opens into FRONT_ENTRAN</b>

DESCRIPTION	QTY
543. Protect contents - Cover with plastic	1955.22 SF
544. HEPA Vacuuming - Detailed - (PER SF)	1039.12 SF
545. Clean more than the floor - Heavy	1955.22 SF
546. Clean floor - tile - Heavy clean	1039.12 SF
547. Apply plant-based anti-microbial agent to the walls	916.10 SF
548. Content Manipulation charge - per hour	1.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
549. Clean suspended ceiling grid	1039.12 SF
550. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
551. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
552. Clean with pressure/chemical spray	4.00 SF
553. Remove susp. ceiling tile, bag for disp. - after hrs	1039.12 SF
554. Material Only Suspended ceiling tile - 2' x 4'	1039.12 SF
555. Install Suspended ceiling tile - 2' x 4'	1039.12 SF
Labor at standard rate	
556. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	1039.12 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### Athletic hall

Height: 9'



1906.50 SF Walls	647.98 SF Ceiling
2554.48 SF Walls & Ceiling	647.98 SF Floor
72.00 SY Flooring	211.83 LF Floor Perimeter
211.83 LF Ceil. Perimeter	

Missing Wall

6' 4" X 9'

Opens into STAIRS1

Missing Wall

6' 3" X 9'

Opens into STAIRS4

### DESCRIPTION

QTY

557. Protect contents - Cover with plastic	2554.48 SF
558. HEPA Vacuuming - Detailed - (PER SF)	647.98 SF
559. Clean more than the floor - Heavy	2554.48 SF
560. Clean floor - tile - Heavy clean	647.98 SF
561. Apply plant-based anti-microbial agent to the walls	1906.50 SF
562. Content Manipulation charge - per hour	1.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
563. Clean suspended ceiling grid	647.98 SF
564. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
565. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
566. Clean with pressure/chemical spray	4.00 SF
567. Remove susp. ceiling tile, bag for disp. - after hrs	647.98 SF
568. Material Only Suspended ceiling tile - 2' x 4'	647.98 SF
569. Install Suspended ceiling tile - 2' x 4'	647.98 SF
Labor at standard rate	
570. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	647.98 SF


NOTES:





# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



## Subroom: Stairs3 (1)

**Height: 12' 6"**

263.43 SF Walls	79.85 SF Ceiling
343.28 SF Walls & Ceiling	112.56 SF Floor
12.51 SY Flooring	26.60 LF Floor Perimeter
25.54 LF Ceil. Perimeter	

Missing Wall

**6' 3 3/4" X 12' 6"**

**Opens into LANDING1**

### DESCRIPTION

### QTY

575. Protect contents - Cover with plastic	1276.79 SF
576. HEPA Vacuuming - Detailed - (PER SF)	304.87 SF
577. Clean more than the floor - Heavy	1276.79 SF
578. Clean floor - tile - Heavy clean	304.87 SF
579. Apply plant-based anti-microbial agent to the walls	971.92 SF
580. Clean suspended ceiling grid	242.07 SF
581. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
582. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
583. Clean with pressure/chemical spray	4.00 SF
584. Remove susp. ceiling tile, bag for disp. - after hrs	242.07 SF
585. Material Only Suspended ceiling tile - 2' x 4'	242.07 SF
586. Install Suspended ceiling tile - 2' x 4'	242.07 SF
Labor at standard rate	
587. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	304.87 SF

NOTES:



## Athletic locker rooms

**Height: 8'**

2262.67 SF Walls	3229.58 SF Ceiling
5492.25 SF Walls & Ceiling	3229.58 SF Floor
358.84 SY Flooring	282.83 LF Floor Perimeter
282.83 LF Ceil. Perimeter	




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

DESCRIPTION	QTY
588. Protect contents - Cover with plastic	5492.25 SF
589. HEPA Vacuuming - Detailed - (PER SF)	3229.58 SF
590. Clean more than the floor - Heavy	5492.25 SF
591. Clean floor - tile - Heavy clean	3229.58 SF
592. Apply plant-based anti-microbial agent to the walls	2262.67 SF
593. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets Remove everything on walls and clean	
594. Clean suspended ceiling grid	3229.58 SF
595. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	6.00 EA
596. Clean with pressure/chemical spray	24.00 SF
597. R&R Ceiling diffusers / grills - square, lay-in - 24"	12.00 EA
598. Remove susp. ceiling tile, bag for disp. - after hrs	3229.58 SF
599. Material Only Suspended ceiling tile - 2' x 4'	3229.58 SF
600. Install Suspended ceiling tile - 2' x 4'	3229.58 SF
Labor at standard rate	
601. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	3229.58 SF

NOTES:



### Stairs1

Height: 17'

388.39 SF Walls	82.47 SF Ceiling
470.87 SF Walls & Ceiling	112.55 SF Floor
12.51 SY Flooring	27.16 LF Floor Perimeter
26.29 LF Ceil. Perimeter	

Missing Wall


6' 3" X 17'

Opens into ATHLETIC\_HAL



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### Subroom: Stairs3 (1)


**Height: 12' 6"**

263.43 SF Walls	78.48 SF Ceiling
341.91 SF Walls & Ceiling	110.74 SF Floor
12.30 SY Flooring	26.60 LF Floor Perimeter
25.54 LF Ceil. Perimeter	

Missing Wall

**6' 1 3/4" X 12' 6"**

**Opens into LANDING2**



### Subroom: Landing1 (2)

**Height: 12' 6"**

313.77 SF Walls	78.67 SF Ceiling
392.43 SF Walls & Ceiling	78.67 SF Floor
8.74 SY Flooring	25.10 LF Floor Perimeter
25.10 LF Ceil. Perimeter	

Missing Wall

**6' 1 3/4" X 12' 6"**

**Opens into STAIRS5**

Missing Wall

**6' 4" X 12' 6"**

**Opens into STAIRS4**

### DESCRIPTION

### QTY

602. Protect contents - Cover with plastic	1267.55 SF
603. HEPA Vacuuming - Detailed - (PER SF)	301.96 SF
604. Clean more than the floor - Heavy	1267.55 SF
605. Clean floor - tile - Heavy clean	301.96 SF
606. Apply plant-based anti-microbial agent to the walls	965.59 SF
607. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
608. Clean suspended ceiling grid	239.62 SF
609. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
610. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
611. Clean with pressure/chemical spray	4.00 SF
612. Remove susp. ceiling tile, bag for disp. - after hrs	239.62 SF
613. Material Only Suspended ceiling tile - 2' x 4'	239.62 SF
614. Install Suspended ceiling tile - 2' x 4'	239.62 SF
Labor at standard rate	
615. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	301.96 SF





## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Stairs1

#### DESCRIPTION

**QTY**

NOTES:

#### Media center corridor

**Height: 9' 11"**

3805.89 SF Walls	2196.07 SF Ceiling
6001.96 SF Walls & Ceiling	2196.07 SF Floor
244.01 SY Flooring	381.50 LF Floor Perimeter
393.33 LF Ceil. Perimeter	

Missing Wall

11' 10" X 9' 11"

Opens into RIGHT\_ENTRAN

#### DESCRIPTION

**QTY**

616. Protect contents - Cover with plastic	6001.96 SF
617. HEPA Vacuuming - Detailed - (PER SF)	2196.07 SF
618. Clean more than the floor - Heavy	6001.96 SF
619. Clean floor - tile - Heavy clean	2196.07 SF
620. Apply plant-based anti-microbial agent to the walls	3805.89 SF
621. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
622. Clean suspended ceiling grid	2196.07 SF
623. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
624. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
625. Clean with pressure/chemical spray	4.00 SF
626. Remove susp. ceiling tile, bag for disp. - after hrs	2196.07 SF
627. Material Only Suspended ceiling tile - 2' x 2'	2196.07 SF
628. Install Suspended ceiling tile - 2' x 2'	2196.07 SF
Labor at standard rate	
629. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	2196.07 SF



# Ram Restoration


2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Media center corridor

### DESCRIPTION

### QTY

NOTES:



### Womans restrooms 1

Height: 9' 6"

1334.39 SF Walls	812.17 SF Ceiling
2146.56 SF Walls & Ceiling	812.17 SF Floor
90.24 SY Flooring	138.97 LF Floor Perimeter
143.97 LF Ceil. Perimeter	

Missing Wall - Goes to Floor

5' X 6' 8"

Opens into RIGHT\_ENTRAN

### DESCRIPTION

### QTY

630. Protect contents - Cover with plastic	2146.56 SF
631. HEPA Vacuuming - Detailed - (PER SF)	812.17 SF
632. Clean more than the floor - Heavy	2146.56 SF
633. Clean floor - tile - Heavy clean	812.17 SF
634. Apply plant-based anti-microbial agent to the walls	1334.39 SF
635. Clean suspended ceiling grid	812.17 SF
636. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
637. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
638. Clean with pressure/chemical spray	4.00 SF
639. Remove susp. ceiling tile, bag for disp. - after hrs	812.17 SF
640. Material Only Suspended ceiling tile - 2' x 4'	812.17 SF
641. Install Suspended ceiling tile - 2' x 4'	812.17 SF
Labor at standard rate	
642. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	812.17 SF



# Ram Restoration


2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Womans restrooms 1

### DESCRIPTION

### QTY

NOTES:



### Mens restrooms 1

Height: 9' 6"

998.25 SF Walls	351.98 SF Ceiling
1350.23 SF Walls & Ceiling	351.98 SF Floor
39.11 SY Flooring	104.30 LF Floor Perimeter
109.25 LF Ceil. Perimeter	

Missing Wall

4' 11 1/2" X 9' 6"

Opens into RIGHT\_ENTRAN

### DESCRIPTION

### QTY

643. Protect contents - Cover with plastic	1350.23 SF
644. HEPA Vacuuming - Detailed - (PER SF)	351.98 SF
645. Clean more than the floor - Heavy	1350.23 SF
646. Clean floor - tile - Heavy clean	351.98 SF
647. Apply plant-based anti-microbial agent to the walls	998.25 SF
648. Clean suspended ceiling grid	351.98 SF
649. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
650. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
651. Clean with pressure/chemical spray	4.00 SF
652. Remove susp. ceiling tile, bag for disp. - after hrs	351.98 SF
653. Material Only Suspended ceiling tile - 2' x 4'	351.98 SF
654. Install Suspended ceiling tile - 2' x 4'	351.98 SF
Labor at standard rate	
655. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	351.98 SF




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Mens restrooms 1

DESCRIPTION	QTY
-------------	-----

NOTES:



### CComputer Lab

**Height: 10' 11"**

1244.50 SF Walls	803.00 SF Ceiling
2047.50 SF Walls & Ceiling	803.00 SF Floor
89.22 SY Flooring	114.00 LF Floor Perimeter
114.00 LF Ceil. Perimeter	

DESCRIPTION	QTY
-------------	-----

656. Protect contents - Cover with plastic	2047.50 SF
657. HEPA Vacuuming - Detailed - (PER SF)	803.00 SF
658. Clean more than the floor - Heavy clean all surfaces in room	2047.50 SF
659. Clean and deodorize carpet	803.00 SF
660. Apply plant-based anti-microbial agent to more than the floor	2047.50 SF
661. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
662. Clean suspended ceiling grid	803.00 SF
663. R&R Ceiling diffusers / grills - square, lay-in - 24"	4.00 EA
664. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
665. Clean with pressure/chemical spray suspending ceiling return vents	8.00 SF
666. Remove susp. ceiling tile, bag for disp. - after hrs	803.00 SF
667. Material Only Suspended ceiling tile - 2' x 4'	803.00 SF
668. Install Suspended ceiling tile - 2' x 4'	803.00 SF
Labor at standard rate	



## Ram Restoration


2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - CComputer Lab

DESCRIPTION	QTY
-------------	-----

669. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	803.00 SF
---	-----------

NOTES:



#### Computer Lab 2

**Height: 10' 11"**

1289.99 SF Walls	817.58 SF Ceiling
2107.57 SF Walls & Ceiling	817.58 SF Floor
90.84 SY Flooring	118.17 LF Floor Perimeter
118.17 LF Ceil. Perimeter	

DESCRIPTION	QTY
-------------	-----

670. Protect contents - Cover with plastic	2107.57 SF
671. HEPA Vacuuming - Detailed - (PER SF)	817.58 SF
672. Clean more than the floor - Heavy clean all surfaces in room	2107.57 SF
673. Clean and deodorize carpet	817.58 SF
674. Apply plant-based anti-microbial agent to more than the floor	2107.57 SF
675. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets Remove everything on walls and clean	
676. Clean suspended ceiling grid	817.58 SF
677. R&R Ceiling diffusers / grills - square, lay-in - 24"	4.00 EA
678. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
679. Clean with pressure/chemical spray suspending ceiling return vents	8.00 SF
680. Remove susp. ceiling tile, bag for disp. - after hrs	817.58 SF
681. Material Only Suspended ceiling tile - 2' x 4'	817.58 SF




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Computer Lab 2

DESCRIPTION	QTY
682. Install Suspended ceiling tile - 2' x 4' Labor at standard rate	817.58 SF
683. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	817.58 SF

NOTES:



#### Media storage

Height: 9'

511.77 SF Walls	197.18 SF Ceiling
708.95 SF Walls & Ceiling	197.18 SF Floor
21.91 SY Flooring	56.86 LF Floor Perimeter
56.86 LF Ceil. Perimeter	

DESCRIPTION	QTY
684. Protect contents - Cover with plastic	708.95 SF
685. HEPA Vacuuming - Detailed - (PER SF)	197.18 SF
686. Clean more than the floor - Heavy clean all surfaces in room	708.95 SF
687. Clean and deodorize carpet	197.18 SF
688. Apply plant-based anti-microbial agent to more than the floor	708.95 SF
689. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
690. Clean suspended ceiling grid	197.18 SF
691. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
692. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
693. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Media storage

DESCRIPTION	QTY
694. Remove susp. ceiling tile, bag for disp. - after hrs	197.18 SF
695. Material Only Suspended ceiling tile - 2' x 4'	197.18 SF
696. Install Suspended ceiling tile - 2' x 4'	197.18 SF
Labor at standard rate	
697. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	197.18 SF

NOTES:



### Media office

Height: 9'

526.39 SF Walls	218.57 SF Ceiling
744.96 SF Walls & Ceiling	218.57 SF Floor
24.29 SY Flooring	58.49 LF Floor Perimeter
58.49 LF Ceil. Perimeter	

DESCRIPTION	QTY
698. Protect contents - Cover with plastic	744.96 SF
699. HEPA Vacuuming - Detailed - (PER SF)	218.57 SF
700. Clean more than the floor - Heavy clean all surfaces in room	744.96 SF
701. Clean and deodorize carpet	218.57 SF
702. Apply plant-based anti-microbial agent to more than the floor	744.96 SF
703. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	4.00 HR
704. Clean suspended ceiling grid	218.57 SF
705. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
706. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Media office

DESCRIPTION	QTY
707. Clean with pressure/chemical spray suspended ceiling return vents	4.00 SF
708. Remove susp. ceiling tile, bag for disp. - after hrs	218.57 SF
709. Material Only Suspended ceiling tile - 2' x 2'	218.57 SF
710. Install Suspended ceiling tile - 2' x 2'	218.57 SF
Labor at standard rate	
711. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	218.57 SF

NOTES:



### Media center

Height: 13' 2"

2047.68 SF Walls	2405.27 SF Ceiling
4452.95 SF Walls & Ceiling	2405.27 SF Floor
267.25 SY Flooring	138.97 LF Floor Perimeter
206.01 LF Ceil. Perimeter	

Missing Wall	51' 8 5/8" X 13' 2"	Opens into MEDIA_CENTE2
Missing Wall	15' 3 13/16" X 13' 2"	Opens into MEDIA_CENTE2

DESCRIPTION	QTY
712. Protect contents - Cover with plastic	4452.95 SF
713. HEPA Vacuuming - Detailed - (PER SF)	2405.27 SF
714. Clean more than the floor - Heavy clean all surfaces in room	4452.95 SF
715. Clean and deodorize carpet	2405.27 SF
716. Apply plant-based anti-microbial agent to more than the floor	4452.95 SF
717. Content Manipulation charge - per hour	24.00 HR






# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Media center

DESCRIPTION	QTY
Box everything in the cabinets	
Remove everything on walls and clean	
718. Clean suspended ceiling grid	2405.27 SF
719. R&R Ceiling diffusers / grills - square, lay-in - 24"	8.00 EA
720. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	3.00 EA
721. Clean with pressure/chemical spray suspending ceiling return vents	12.00 SF
722. Remove susp. ceiling tile, bag for disp. - after hrs	2405.27 SF
723. Material Only Suspended ceiling tile - 2' x 2'	2405.27 SF
724. Install Suspended ceiling tile - 2' x 2'	2405.27 SF
Labor at standard rate	
725. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	2405.27 SF

NOTES:



### Media center entrance

Height: 9' 11"

989.52 SF Walls	502.22 SF Ceiling
1491.74 SF Walls & Ceiling	502.22 SF Floor
55.80 SY Flooring	99.78 LF Floor Perimeter
99.78 LF Ceil. Perimeter	

Missing Wall	15' 3 13/16" X 9' 11"	Opens into MEDIA_CENTE1
Missing Wall	51' 8 5/8" X 9' 11"	Opens into MEDIA_CENTE1

DESCRIPTION	QTY
726. Protect contents - Cover with plastic	1491.74 SF
727. HEPA Vacuuming - Detailed - (PER SF)	502.22 SF
728. Clean more than the floor - Heavy	1491.74 SF




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Media center entrance

DESCRIPTION	QTY
clean all surfaces in room	
729. Clean and deodorize carpet	502.22 SF
730. Apply plant-based anti-microbial agent to more than the floor	1491.74 SF
731. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
732. Clean suspended ceiling grid	502.22 SF
733. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
734. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
735. Clean with pressure/chemical spray	4.00 SF
suspending ceiling return vents	
736. Remove susp. ceiling tile, bag for disp. - after hrs	502.22 SF
737. Material Only Suspended ceiling tile - 2' x 2'	502.22 SF
738. Install Suspended ceiling tile - 2' x 2'	502.22 SF
Labor at standard rate	
739. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	502.22 SF

NOTES:



#### Conference room

Height: 9' 11"

747.72 SF Walls	305.38 SF Ceiling
1053.10 SF Walls & Ceiling	305.38 SF Floor
33.93 SY Flooring	75.40 LF Floor Perimeter
75.40 LF Ceil. Perimeter	

DESCRIPTION	QTY
740. Protect contents - Cover with plastic	1053.10 SF




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Confrence room

DESCRIPTION	QTY
741. HEPA Vacuuming - Detailed - (PER SF)	305.38 SF
742. Clean more than the floor - Heavy clean all surfaces in room	1053.10 SF
743. Clean and deodorize carpet	305.38 SF
744. Apply plant-based anti-microbial agent to more than the floor	1053.10 SF
745. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	6.00 HR
746. Clean suspended ceiling grid	305.38 SF
747. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
748. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
749. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
750. Remove susp. ceiling tile, bag for disp. - after hrs	305.38 SF
751. Material Only Suspended ceiling tile - 2' x 2'	305.38 SF
752. Install Suspended ceiling tile - 2' x 2'	305.38 SF
Labor at standard rate	
753. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	305.38 SF

NOTES:



### Library

**Height: 9' 11"**

1386.68 SF Walls	1212.83 SF Ceiling
2599.51 SF Walls & Ceiling	1212.83 SF Floor
134.76 SY Flooring	139.83 LF Floor Perimeter
139.83 LF Ceil. Perimeter	



## Ram Restoration

2800 East River Road Suite A  
Dayton, Ohio 45439  
RamRestorationUSA.com  
(937) 885-0088

DESCRIPTION	QTY
754. Protect contents - Cover with plastic	2599.51 SF
755. HEPA Vacuuming - Detailed - (PER SF)	1212.83 SF
756. Clean more than the floor - Heavy clean all surfaces in room	2599.51 SF
757. Clean and deodorize carpet	1212.83 SF
758. Apply plant-based anti-microbial agent to more than the floor	2599.51 SF
759. Content Manipulation charge - per hour Box everything in the cabinets Remove everything on walls and clean	8.00 HR
760. Clean suspended ceiling grid	1212.83 SF
761. R&R Ceiling diffusers / grills - square, lay-in - 24"	4.00 EA
762. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
763. Clean with pressure/chemical spray suspending ceiling return vents	8.00 SF
764. Remove susp. ceiling tile, bag for disp. - after hrs	1212.83 SF
765. Material Only Suspended ceiling tile - 2' x 2'	1212.83 SF
766. Install Suspended ceiling tile - 2' x 2' Labor at standard rate	1212.83 SF
767. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	1212.83 SF

NOTES:

### Level 2

#### Level 2


DESCRIPTION	QTY
768. Neg. air fan/Air scrub.-Large (per 24 hr period)-No monit.	160.00 DA
769. Add for HEPA filter (for negative air exhaust fan)	3.20 EA
770. Hydroxyl generator - odor counteractant - 2 optics	32.00 DA

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



21

Height: 8' 10"

984.92 SF Walls	776.97 SF Ceiling
1761.89 SF Walls & Ceiling	776.97 SF Floor
86.33 SY Flooring	111.50 LF Floor Perimeter
111.50 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


771. Protect contents - Cover with plastic	1761.89 SF
772. HEPA Vacuuming - Detailed - (PER SF)	776.97 SF
773. Clean more than the floor - Heavy	1761.89 SF
774. Clean and deodorize carpet	776.97 SF
775. Apply plant-based anti-microbial agent to the walls	984.92 SF
776. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
777. Clean suspended ceiling grid	776.97 SF
778. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
779. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
780. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
781. Remove susp. ceiling tile, bag for disp. - after hrs	776.97 SF
782. Material Only Suspended ceiling tile - 2' x 4'	776.97 SF
783. Install Suspended ceiling tile - 2' x 4'	776.97 SF
Labor at standard rate	
784. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	776.97 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



22

Height: 8' 10"

1021.72 SF Walls	835.33 SF Ceiling
1857.06 SF Walls & Ceiling	835.33 SF Floor
92.81 SY Flooring	115.67 LF Floor Perimeter
115.67 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


785. Protect contents - Cover with plastic	1857.06 SF
786. HEPA Vacuuming - Detailed - (PER SF)	835.33 SF
787. Clean more than the floor - Heavy	1857.06 SF
788. Clean and deodorize carpet	835.33 SF
789. Apply plant-based anti-microbial agent to the walls	1021.72 SF
790. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
791. Clean suspended ceiling grid	835.33 SF
792. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
793. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
794. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
795. Remove susp. ceiling tile, bag for disp. - after hrs	835.33 SF
796. Material Only Suspended ceiling tile - 2' x 4'	835.33 SF
797. Install Suspended ceiling tile - 2' x 4'	835.33 SF
Labor at standard rate	
798. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	835.33 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



**23**

**Height: 8' 10"**

984.92 SF Walls	776.97 SF Ceiling
1761.89 SF Walls & Ceiling	776.97 SF Floor
86.33 SY Flooring	111.50 LF Floor Perimeter
111.50 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


799. Protect contents - Cover with plastic	1761.89 SF
800. HEPA Vacuuming - Detailed - (PER SF)	776.97 SF
801. Clean more than the floor - Heavy	1761.89 SF
802. Clean and deodorize carpet	776.97 SF
803. Apply plant-based anti-microbial agent to the walls	984.92 SF
804. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
805. Clean suspended ceiling grid	776.97 SF
806. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
807. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
808. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
809. Remove susp. ceiling tile, bag for disp. - after hrs	776.97 SF
810. Material Only Suspended ceiling tile - 2' x 4'	776.97 SF
811. Install Suspended ceiling tile - 2' x 4'	776.97 SF
Labor at standard rate	
812. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	776.97 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



**24**

**Height: 8' 10"**

987.86 SF Walls	778.15 SF Ceiling
1766.01 SF Walls & Ceiling	778.15 SF Floor
86.46 SY Flooring	111.83 LF Floor Perimeter
111.83 LF Ceil. Perimeter	

### DESCRIPTION

### QTY

813. Protect contents - Cover with plastic	1766.01 SF
814. HEPA Vacuuming - Detailed - (PER SF)	778.15 SF
815. Clean more than the floor - Heavy	1766.01 SF
816. Clean and deodorize carpet	778.15 SF
817. Apply plant-based anti-microbial agent to the walls	987.86 SF
818. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
819. Clean suspended ceiling grid	778.15 SF
820. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
821. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
822. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
823. Remove susp. ceiling tile, bag for disp. - after hrs	778.15 SF
824. Material Only Suspended ceiling tile - 2' x 4'	778.15 SF
825. Install Suspended ceiling tile - 2' x 4'	778.15 SF
Labor at standard rate	
826. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	778.15 SF


NOTES:





## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



25

**Height: 8' 10"**

984.92 SF Walls	776.97 SF Ceiling
1761.89 SF Walls & Ceiling	776.97 SF Floor
86.33 SY Flooring	111.50 LF Floor Perimeter
111.50 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


827. Protect contents - Cover with plastic	1761.89 SF
828. HEPA Vacuuming - Detailed - (PER SF)	776.97 SF
829. Clean more than the floor - Heavy	1761.89 SF
830. Clean and deodorize carpet	776.97 SF
831. Apply plant-based anti-microbial agent to the walls	984.92 SF
832. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
833. Clean suspended ceiling grid	776.97 SF
834. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
835. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
836. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
837. Remove susp. ceiling tile, bag for disp. - after hrs	776.97 SF
838. Material Only Suspended ceiling tile - 2' x 4'	776.97 SF
839. Install Suspended ceiling tile - 2' x 4'	776.97 SF
Labor at standard rate	
840. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	776.97 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



26

Height: 8' 10"

987.86 SF Walls	778.15 SF Ceiling
1766.01 SF Walls & Ceiling	778.15 SF Floor
86.46 SY Flooring	111.83 LF Floor Perimeter
111.83 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


841. Protect contents - Cover with plastic	1766.01 SF
842. HEPA Vacuuming - Detailed - (PER SF)	778.15 SF
843. Clean more than the floor - Heavy	1766.01 SF
844. Clean and deodorize carpet	778.15 SF
845. Apply plant-based anti-microbial agent to the walls	987.86 SF
846. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
847. Clean suspended ceiling grid	778.15 SF
848. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
849. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
850. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
851. Remove susp. ceiling tile, bag for disp. - after hrs	778.15 SF
852. Material Only Suspended ceiling tile - 2' x 4'	778.15 SF
853. Install Suspended ceiling tile - 2' x 4'	778.15 SF
Labor at standard rate	
854. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	778.15 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



27

Height: 8' 10"

984.92 SF Walls	776.97 SF Ceiling
1761.89 SF Walls & Ceiling	776.97 SF Floor
86.33 SY Flooring	111.50 LF Floor Perimeter
111.50 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


855. Protect contents - Cover with plastic	1761.89 SF
856. HEPA Vacuuming - Detailed - (PER SF)	776.97 SF
857. Clean more than the floor - Heavy	1761.89 SF
858. Clean and deodorize carpet	776.97 SF
859. Apply plant-based anti-microbial agent to the walls	984.92 SF
860. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
861. Clean suspended ceiling grid	776.97 SF
862. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
863. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
864. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
865. Remove susp. ceiling tile, bag for disp. - after hrs	776.97 SF
866. Material Only Suspended ceiling tile - 2' x 4'	776.97 SF
867. Install Suspended ceiling tile - 2' x 4'	776.97 SF
Labor at standard rate	
868. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	776.97 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



**28**

**Height: 8' 10"**

1017.31 SF Walls	827.88 SF Ceiling
1845.18 SF Walls & Ceiling	827.88 SF Floor
91.99 SY Flooring	115.17 LF Floor Perimeter
115.17 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


869. Protect contents - Cover with plastic	1845.18 SF
870. HEPA Vacuuming - Detailed - (PER SF)	827.88 SF
871. Clean more than the floor - Heavy	1845.18 SF
872. Clean and deodorize carpet	827.88 SF
873. Apply plant-based anti-microbial agent to the walls	1017.31 SF
874. Electrician - per hour	1.00 HR
875. Clean with pressure/chemical spray	4.00 SF
876. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
877. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
878. Clean suspended ceiling grid	827.88 SF
Box everything in the cabinets	
Remove everything on walls and clean	
879. Content Manipulation charge - per hour	6.00 HR
880. Remove susp. ceiling tile, bag for disp. - after hrs	827.88 SF
881. Material Only Suspended ceiling tile - 2' x 4'	827.88 SF
882. Install Suspended ceiling tile - 2' x 4'	827.88 SF
Labor at standard rate	
883. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	827.88 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### Tutoring room

**Height: 8' 10"**

742.00 SF Walls	432.00 SF Ceiling
1174.00 SF Walls & Ceiling	432.00 SF Floor
48.00 SY Flooring	84.00 LF Floor Perimeter
84.00 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


884. Protect contents - Cover with plastic	1174.00 SF
885. HEPA Vacuuming - Detailed - (PER SF)	432.00 SF
886. Clean more than the floor - Heavy	1174.00 SF
887. Apply plant-based anti-microbial agent to the walls	742.00 SF
888. Clean floor - tile - Heavy clean	432.00 SF
889. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
890. Clean suspended ceiling grid	432.00 SF
891. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
892. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
893. Clean with pressure/chemical spray suspending ceiling return vents	4.00 SF
894. Remove susp. ceiling tile, bag for disp. - after hrs	432.00 SF
895. Material Only Suspended ceiling tile - 2' x 4'	432.00 SF
896. Install Suspended ceiling tile - 2' x 4'	432.00 SF
Labor at standard rate	
897. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	432.00 SF

NOTES:



# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



## Biology Lab

**Height: 8'**

1208.28 SF Walls	1318.85 SF Ceiling
2527.13 SF Walls & Ceiling	1318.85 SF Floor
146.54 SY Flooring	151.03 LF Floor Perimeter
151.03 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


898. Protect contents - Cover with plastic	2527.13 SF
899. HEPA Vacuuming - Detailed - (PER SF)	1318.85 SF
900. Clean more than the floor - Heavy	2527.13 SF
901. Apply plant-based anti-microbial agent to the walls	1208.28 SF
902. Content Manipulation charge - per hour	6.00 HR
Box everything in the cabinets	
Remove everything on walls and clean	
903. Clean suspended ceiling grid	1318.85 SF
904. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
905. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
906. Clean with pressure/chemical spray	4.00 SF
suspending ceiling return vents	
907. Clean floor - tile - Heavy clean	1318.85 SF
908. Remove susp. ceiling tile, bag for disp. - after hrs	1318.85 SF
909. Material Only Suspended ceiling tile - 2' x 4'	1318.85 SF
910. Install Suspended ceiling tile - 2' x 4'	1318.85 SF
Labor at standard rate	
911. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	1318.85 SF

### NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### Biology prep

**Height: 8'**

465.79 SF Walls	135.88 SF Ceiling
601.68 SF Walls & Ceiling	135.88 SF Floor
15.10 SY Flooring	58.22 LF Floor Perimeter
58.22 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


912. Protect contents - Cover with plastic	601.68 SF
913. HEPA Vacuuming - Detailed - (PER SF)	135.88 SF
914. Clean more than the floor - Heavy	601.68 SF
915. Apply plant-based anti-microbial agent to the walls	465.79 SF
916. Clean floor - tile - Heavy clean	135.88 SF
917. Clean with pressure/chemical spray	4.00 SF
918. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
919. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
920. Clean suspended ceiling grid	135.88 SF
Box everything in the cabinets	
Remove everything on walls and clean	
921. Content Manipulation charge - per hour	6.00 HR
922. Remove susp. ceiling tile, bag for disp. - after hrs	135.88 SF
923. Material Only Suspended ceiling tile - 2' x 4'	135.88 SF
924. Install Suspended ceiling tile - 2' x 4'	135.88 SF
Labor at standard rate	
925. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	135.88 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### Biology lab 2

**Height: 8' 10"**

1335.99 SF Walls	1306.40 SF Ceiling
2642.39 SF Walls & Ceiling	1306.40 SF Floor
145.16 SY Flooring	151.24 LF Floor Perimeter
151.24 LF Ceil. Perimeter	

### DESCRIPTION

### QTY

926. Protect contents - Cover with plastic	5284.78 SF
927. HEPA Vacuuming - Detailed - (PER SF)	2612.79 SF
928. Clean more than the floor - Heavy	5284.78 SF
929. Apply plant-based anti-microbial agent to more than the walls	2671.98 SF
930. Clean floor - tile - Heavy clean	1306.40 SF
931. Clean with pressure/chemical spray	4.00 SF
932. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
933. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
934. Clean suspended ceiling grid	1306.40 SF
Box everything in the cabinets	
Remove everything on walls and clean	
935. Content Manipulation charge - per hour	6.00 HR
936. Remove susp. ceiling tile, bag for disp. - after hrs	1306.40 SF
937. Material Only Suspended ceiling tile - 2' x 4'	1306.40 SF
938. Install Suspended ceiling tile - 2' x 4'	1306.40 SF
Labor at standard rate	
939. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	1306.40 SF


### NOTES:





## Ram Restoration


2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### Lab 3

**Height: 8' 10"**

1273.47 SF Walls	1163.56 SF Ceiling
2437.03 SF Walls & Ceiling	1163.56 SF Floor
129.28 SY Flooring	144.17 LF Floor Perimeter
144.17 LF Ceil. Perimeter	



### Subroom: Lab 3 back room (1)

**Height: 8'**

434.01 SF Walls	167.23 SF Ceiling
601.24 SF Walls & Ceiling	167.23 SF Floor
18.58 SY Flooring	54.25 LF Floor Perimeter
54.25 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


940. Protect contents - Cover with plastic	3038.26 SF
941. HEPA Vacuuming - Detailed - (PER SF)	1330.78 SF
942. Clean more than the floor - Heavy	3038.26 SF
943. Clean floor - tile - Heavy clean	1330.78 SF
944. Apply plant-based anti-microbial agent to the walls	1707.48 SF
945. Clean with pressure/chemical spray	4.00 SF
946. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
947. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
948. Clean suspended ceiling grid	1330.78 SF
Box everything in the cabinets	
Remove everything on walls and clean	
949. Content Manipulation charge - per hour	6.00 HR
950. Remove susp. ceiling tile, bag for disp. - after hrs	1330.78 SF
951. Material Only Suspended ceiling tile - 2' x 4'	1330.78 SF
952. Install Suspended ceiling tile - 2' x 4'	1330.78 SF
Labor at standard rate	
953. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	1330.78 SF

NOTES:



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



### lab back rm

**Height: 8' 10"**

358.09 SF Walls	102.71 SF Ceiling
460.80 SF Walls & Ceiling	102.71 SF Floor
11.41 SY Flooring	40.54 LF Floor Perimeter
40.54 LF Ceil. Perimeter	

### DESCRIPTION

### QTY


954. Protect contents - Cover with plastic	460.80 SF
955. HEPA Vacuuming - Detailed - (PER SF)	102.71 SF
956. Clean more than the floor - Heavy	460.80 SF
957. Clean floor - tile - Heavy clean	102.71 SF
958. Apply plant-based anti-microbial agent to the walls	358.09 SF
959. Clean with pressure/chemical spray	4.00 SF
960. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
961. R&R Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
962. Clean suspended ceiling grid	102.71 SF
Box everything in the cabinets	
Remove everything on walls and clean	
963. Content Manipulation charge - per hour	6.00 HR
964. Remove susp. ceiling tile, bag for disp. - after hrs	102.71 SF
965. Material Only Suspended ceiling tile - 2' x 4'	102.71 SF
966. Install Suspended ceiling tile - 2' x 4'	102.71 SF
Labor at standard rate	
967. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	102.71 SF

### NOTES:



# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088



Missing Wall


## Stairs

Height: 17'

240.92 SF Walls	51.04 SF Ceiling
291.96 SF Walls & Ceiling	80.73 SF Floor
8.97 SY Flooring	18.06 LF Floor Perimeter
16.33 LF Ceil. Perimeter	

6' 3" X 17'

Opens into LEFT\_STAIRWE



Missing Wall

## Subroom: Landing (2)

Height: 12' 6"

330.21 SF Walls	87.13 SF Ceiling
417.33 SF Walls & Ceiling	87.13 SF Floor
9.68 SY Flooring	26.42 LF Floor Perimeter
26.42 LF Ceil. Perimeter	


5' 10" X 12' 6"

Opens into STAIRS2

Missing Wall

6' 3" X 12' 6"

Opens into STAIRS



Missing Wall

## Subroom: Stairs2 (1)

Height: 12' 6"

231.87 SF Walls	56.39 SF Ceiling
288.26 SF Walls & Ceiling	86.92 SF Floor
9.66 SY Flooring	25.03 LF Floor Perimeter
23.67 LF Ceil. Perimeter	

5' 10" X 12' 6"

Opens into LANDING

## DESCRIPTION

QTY

968. Protect contents - Cover with plastic	1057.77 SF
969. HEPA Vacuuming - Detailed - (PER SF)	254.77 SF
970. Clean more than the floor - Heavy	1057.77 SF
971. Clean floor - tile - Heavy clean	254.77 SF
972. Apply plant-based anti-microbial agent to the walls	802.99 SF
973. Clean with pressure/chemical spray	4.00 SF
974. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
975. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
976. Clean suspended ceiling grid	194.56 SF
Box everything in the cabinets	
Remove everything on walls and clean	




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Stairs

DESCRIPTION	QTY
977. Remove susp. ceiling tile, bag for disp. - after hrs	194.56 SF
978. Material Only Suspended ceiling tile - 2' x 4'	194.56 SF
979. Install Suspended ceiling tile - 2' x 4'	194.56 SF
Labor at standard rate	
980. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	254.77 SF

NOTES:



### Left stairwell

Height: 9'

408.75 SF Walls	152.73 SF Ceiling
561.48 SF Walls & Ceiling	152.73 SF Floor
16.97 SY Flooring	45.42 LF Floor Perimeter
45.42 LF Ceil. Perimeter	

Missing Wall

6' 3" X 9'

Opens into STAIRS

DESCRIPTION	QTY
981. Protect contents - Cover with plastic	561.48 SF
982. HEPA Vacuuming - Detailed - (PER SF)	152.73 SF
983. Clean more than the floor - Heavy	561.48 SF
984. Clean floor - stone - Heavy clean	152.73 SF
985. Apply plant-based anti-microbial agent to the walls	408.75 SF
986. Clean with pressure/chemical spray	4.00 SF
987. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
988. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
989. Clean suspended ceiling grid	152.73 SF
Box everything in the cabinets	
Remove everything on walls and clean	




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Left stairwell

DESCRIPTION	QTY
990. Content Manipulation charge - per hour	6.00 HR
991. Remove susp. ceiling tile, bag for disp. - after hrs	152.73 SF
992. Material Only Suspended ceiling tile - 2' x 4'	152.73 SF
993. Install Suspended ceiling tile - 2' x 4'	152.73 SF
Labor at standard rate	
994. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	152.73 SF

NOTES:



### Staircorridor

Height: 8' 9"

333.96 SF Walls	157.00 SF Ceiling
490.96 SF Walls & Ceiling	157.00 SF Floor
17.44 SY Flooring	38.17 LF Floor Perimeter
38.17 LF Ceil. Perimeter	

Missing Wall

12' X 8' 9"

Opens into CORRIDOR\_MAI

DESCRIPTION	QTY
995. Protect contents - Cover with plastic	490.96 SF
996. HEPA Vacuuming - Detailed - (PER SF)	157.00 SF
997. Clean more than the floor - Heavy	490.96 SF
998. Clean floor - tile - Heavy clean	157.00 SF
999. Apply plant-based anti-microbial agent to the walls	333.96 SF
1,000. Clean with pressure/chemical spray	4.00 SF
1,001. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
1,002. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
1,003. Clean suspended ceiling grid	157.00 SF



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Staircorridor

DESCRIPTION	QTY
Box everything in the cabinets	
Remove everything on walls and clean	
1,004. Remove susp. ceiling tile, bag for disp. - after hrs	157.00 SF
1,005. Material Only Suspended ceiling tile - 2' x 4'	157.00 SF
1,006. Install Suspended ceiling tile - 2' x 4'	157.00 SF
Labor at standard rate	
1,007. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	157.00 SF

NOTES:

#### Corridor main

Height: 8' 10"

Left Stairwell / Stair Corridor, Central Hall, Upstairs ocasson

2771.72 SF Walls	1882.00 SF Ceiling
4653.72 SF Walls & Ceiling	1882.00 SF Floor
209.11 SY Flooring	313.67 LF Floor Perimeter
325.67 LF Ceil. Perimeter	

Missing Wall	12' X 8' 10"	Opens into STAIRCORRID
Missing Wall	12' X 8' 10"	Opens into UPSTAIRS_OC1

DESCRIPTION	QTY
1,008. Protect contents - Cover with plastic	4653.72 SF
1,009. HEPA Vacuuming - Detailed - (PER SF)	1882.00 SF
1,010. Clean more than the floor - Heavy	4653.72 SF
1,011. Clean floor - tile - Heavy clean	1882.00 SF
1,012. Apply plant-based anti-microbial agent to the walls	2771.72 SF
1,013. Clean with pressure/chemical spray	4.00 SF
1,014. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
1,015. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Corridor main

DESCRIPTION	QTY
1,016. Clean suspended ceiling grid	1882.00 SF
Box everything in the cabinets	
Remove everything on walls and clean	
1,017. Content Manipulation charge - per hour	2.00 HR
1,018. Remove susp. ceiling tile, bag for disp. - after hrs	1882.00 SF
1,019. Material Only Suspended ceiling tile - 2' x 4'	1882.00 SF
1,020. Install Suspended ceiling tile - 2' x 4'	1882.00 SF
Labor at standard rate	
1,021. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	1882.00 SF

NOTES:



### Upstairs octagon 2

Height: 9' 6"

743.36 SF Walls	621.21 SF Ceiling
1364.58 SF Walls & Ceiling	621.21 SF Floor
69.02 SY Flooring	75.73 LF Floor Perimeter
98.37 LF Ceil. Perimeter	

Missing Wall

12' X 9' 6"

Opens into CORRIDOR\_MAI

Missing Wall

10' 7 3/4" X 9' 6"

Opens into UPSTAIRS\_COR

DESCRIPTION	QTY
1,022. Protect contents - Cover with plastic	1364.58 SF
1,023. HEPA Vacuuming - Detailed - (PER SF)	621.21 SF
1,024. Clean more than the floor - Heavy	1364.58 SF
1,025. Clean floor - tile - Heavy clean	621.21 SF
1,026. Apply plant-based anti-microbial agent to the walls	743.36 SF
1,027. Clean with pressure/chemical spray	4.00 SF



## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Upstairs octagon 2

DESCRIPTION	QTY
1,028. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
1,029. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
1,030. Clean suspended ceiling grid	621.21 SF
Box everything in the cabinets Remove everything on walls and clean	
1,031. Remove susp. ceiling tile, bag for disp. - after hrs	621.21 SF
1,032. Material Only Suspended ceiling tile - 2' x 2'	621.21 SF
1,033. Install Suspended ceiling tile - 2' x 2'	621.21 SF
Labor at standard rate	
1,034. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	621.21 SF

NOTES:



### Mens restrooms

Height: 8' 10"

686.06 SF Walls	268.50 SF Ceiling
954.56 SF Walls & Ceiling	268.50 SF Floor
29.83 SY Flooring	77.67 LF Floor Perimeter
77.67 LF Ceil. Perimeter	

DESCRIPTION	QTY
1,035. Protect contents - Cover with plastic	954.56 SF
1,036. HEPA Vacuuming - Detailed - (PER SF)	268.50 SF
1,037. Clean more than the floor - Heavy	954.56 SF
1,038. Clean floor - tile - Heavy clean	268.50 SF
1,039. Apply plant-based anti-microbial agent to the walls	686.06 SF
1,040. Content Manipulation charge - per hour	6.00 HR





# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Mens restrooms

DESCRIPTION	QTY
Box everything in the cabinets	
Remove everything on walls and clean	
1,041. Clean suspended ceiling grid	268.50 SF
1,042. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
1,043. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
1,044. Clean with pressure/chemical spray	4.00 SF
1,045. Remove susp. ceiling tile, bag for disp. - after hrs	268.50 SF
1,046. Material Only Suspended ceiling tile - 2' x 4'	268.50 SF
1,047. Install Suspended ceiling tile - 2' x 4'	268.50 SF
Labor at standard rate	
1,048. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	268.50 SF

NOTES:



### Womans restroom

Height: 8' 10"

686.06 SF Walls	268.50 SF Ceiling
954.56 SF Walls & Ceiling	268.50 SF Floor
29.83 SY Flooring	77.67 LF Floor Perimeter
77.67 LF Ceil. Perimeter	

DESCRIPTION	QTY
1,049. Protect contents - Cover with plastic	954.56 SF
1,050. HEPA Vacuuming - Detailed - (PER SF)	268.50 SF
1,051. Clean more than the floor - Heavy	954.56 SF
1,052. Clean floor - tile - Heavy clean	268.50 SF
1,053. Apply plant-based anti-microbial agent to the walls	686.06 SF
1,054. Clean with pressure/chemical spray	4.00 SF




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Womans restroom

DESCRIPTION	QTY
1,055. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
1,056. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
1,057. Clean suspended ceiling grid	268.50 SF
Box everything in the cabinets Remove everything on walls and clean	
1,058. Remove susp. ceiling tile, bag for disp. - after hrs	268.50 SF
1,059. Material Only Suspended ceiling tile - 2' x 4'	268.50 SF
1,060. Install Suspended ceiling tile - 2' x 4'	268.50 SF
Labor at standard rate	
1,061. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	268.50 SF

#### NOTES:



#### Upstairs corridor small

**Height: 8'**

329.23 SF Walls	220.43 SF Ceiling
549.66 SF Walls & Ceiling	220.43 SF Floor
24.49 SY Flooring	41.15 LF Floor Perimeter
41.15 LF Ceil. Perimeter	

Missing Wall

10' 9 15/16" X 8'

Opens into UPSTAIRS\_OC1

Missing Wall

11' 1 1/4" X 8'

Opens into UPSTAIRS\_OCT

DESCRIPTION	QTY
1,062. Protect contents - Cover with plastic	549.66 SF
1,063. HEPA Vacuuming - Detailed - (PER SF)	220.43 SF
1,064. Clean more than the floor - Heavy	549.66 SF
1,065. Clean floor - tile - Heavy clean	220.43 SF
1,066. Apply plant-based anti-microbial agent to the walls	329.23 SF




# Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

## CONTINUED - Upstairs corridor small

DESCRIPTION	QTY
1,067. Clean with pressure/chemical spray	4.00 SF
1,068. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
1,069. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
1,070. Clean suspended ceiling grid	220.43 SF
Box everything in the cabinets Remove everything on walls and clean	
1,071. Remove susp. ceiling tile, bag for disp. - after hrs	220.43 SF
1,072. Material Only Suspended ceiling tile - 2' x 4'	220.43 SF
1,073. Install Suspended ceiling tile - 2' x 4'	220.43 SF
Labor at standard rate	
1,074. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	220.43 SF

NOTES:



### Upstairs Octagon 1

Height: 9' 6"

704.90 SF Walls	517.83 SF Ceiling
1222.73 SF Walls & Ceiling	517.83 SF Floor
57.54 SY Flooring	72.45 LF Floor Perimeter
83.55 LF Ceil. Perimeter	

Missing Wall

11' 1 1/4" X 9' 6"

Opens into UPSTAIRS\_COR

DESCRIPTION	QTY
1,075. Protect contents - Cover with plastic	1222.73 SF
1,076. HEPA Vacuuming - Detailed - (PER SF)	517.83 SF
1,077. Clean more than the floor - Heavy	1222.73 SF
1,078. Clean floor - tile - Heavy clean	517.83 SF
1,079. Apply plant-based anti-microbial agent to the walls	704.90 SF




## Ram Restoration

2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Upstairs Octagon 1

DESCRIPTION	QTY
1,080. Clean with pressure/chemical spray	4.00 SF
1,081. Detach & Reset Ceiling diffusers / grills - square, lay-in - 24"	1.00 EA
1,082. R&R Ceiling diffusers / grills - square, lay-in - 24"	2.00 EA
1,083. Clean suspended ceiling grid	517.83 SF
Box everything in the cabinets Remove everything on walls and clean	
1,084. Content Manipulation charge - per hour	6.00 HR
1,085. Remove susp. ceiling tile, bag for disp. - after hrs	517.83 SF
1,086. Material Only Suspended ceiling tile - 2' x 2'	517.83 SF
1,087. Install Suspended ceiling tile - 2' x 2'	517.83 SF
Labor at standard rate	
1,088. Acoustical Treatments Installer - additional labor at overtime to complete project on schedule	517.83 SF

NOTES:



### Running Track

Height: 8'

6403.55 SF Walls	2916.12 SF Ceiling
9319.67 SF Walls & Ceiling	2916.12 SF Floor
324.01 SY Flooring	800.44 LF Floor Perimeter
800.44 LF Ceil. Perimeter	

DESCRIPTION	QTY
1,089. HEPA Vacuuming - Detailed - (PER SF)	2916.12 SF
1,090. Clean the floor	2916.12 SF
1,091. Apply plant-based anti-microbial agent to the floor	2916.12 SF



## Ram Restoration


2800 East River Road Suite A  
 Dayton, Ohio 45439  
 RamRestorationUSA.com  
 (937) 885-0088

### CONTINUED - Running Track

#### DESCRIPTION

**QTY**

NOTES:



#### Workout room

**Height: 8'**

2197.33 SF Walls	2402.72 SF Ceiling
4600.05 SF Walls & Ceiling	2402.72 SF Floor
266.97 SY Flooring	274.67 LF Floor Perimeter
274.67 LF Ceil. Perimeter	

#### DESCRIPTION

**QTY**

1,092. HEPA Vacuuming - Detailed - (PER SF)	2402.72 SF
1,093. Clean more than the floor - Heavy	4600.05 SF
1,094. Apply plant-based anti-microbial agent to the walls	2197.33 SF
1,095. Content Manipulation charge - per hour	8.00 HR

NOTES:



## Ram Restoration

---

2800 East River Road Suite A  
Dayton, Ohio 45439  
RamRestorationUSA.com  
(937) 885-0088

### Grand Total Areas:

82,206.47	SF Walls	61,599.69	SF Ceiling	143,806.15	SF Walls and Ceiling
61,845.26	SF Floor	6,871.70	SY Flooring	9,123.47	LF Floor Perimeter
0.00	SF Long Wall	0.00	SF Short Wall	9,314.53	LF Ceil. Perimeter
61,845.26	Floor Area	65,060.74	Total Area	77,516.43	Interior Wall Area
34,423.63	Exterior Wall Area	3,585.03	Exterior Perimeter of Walls		
0.00	Surface Area	0.00	Number of Squares	0.00	Total Perimeter Length
0.00	Total Ridge Length	0.00	Total Hip Length		

